BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/09/2012-13, Date:16.03.2013 Item No: 07

SCHEDULE-B

E OF WORK:Ward Maintenance of Ward Using Tractor, Silt & Labors in Ward No.13, in Shettyhalli Sub Division.

o	Description of work	Unit	Qty	Rates Quoted by Contractor **Sri R MANGALARAJU**		
				In Figures (Rs.)	In Words (Rs.)	Amount
1	2	3	4	5	6	7
1	Supply of the 50HP Tractor on daily rate basis to the required place as per the direction of the Engineer in charge.	Month	348.00	2240.00	Rupees Two Thousand Two Hundred Forty Only	779520.00
2	Supply of the Labour Heavy Mazdoor to the required place as per the direction of the engineer in charge	Days	3480.00	170.00	Rupees One Hundred Seventy Only	591600.00
3	JCB Excavator	Days	15.00	6500.00	Rupees Six Thousand Five Hundred Only	97500.00
4	Tipper	Days	14.00	1920.00	Rupees One Thousand Nine Hundred Twenty Only	26880.00
5	Removing and resetting of footpath slab.	Sqm	694.00	88.56	Rupees Eighty Eight and Fifty Six Paise Only	61460.64
6	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20 mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase lintels retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	10.71	4900.00	Rupees Four Thousand Nine Hundred Only	52479.00

Signature of the Contractor

Executive Engineer

9.2: Providing T.M.T steel reinforcement for work including straightening, cutting, bending, ing, placing in position, lapping and / or welding rever required, tying with binding wire and choring to the adjoining members wherever cessary complete as per design (laps, hooks and vastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Q	8.03	7050.00	Rupees Seven Thousand Fifty Only	56611.50
Removing B.S.Slab of drain and stacking.	Sqm	204.12	43.65	Rupees Forty Three and Sixty Five Paise Only	8909.84
Refixing stone slabs of drains and pointing in CM	Sqm	204.12	61.83	Rupees Sixty One and Eighty Three Paise Only	12620.74
Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	32.40	1600.00	Rupees One Thousand Six Hundred Only	51840.00
Providing Granite slabs of selected quality roughly ressed and fixed in cement mortar (1:6) including xing curing etc., complete. 7.5 cms thick complete s per specifications.	Sqm	22.68	309.52	Rupees Three Hundred Nine and Fifty Two Paise Only	7019.91
				Total	1746441.63
				Percentage	-2.95%

ture of the Contractor

Executive Engineer,
Dasarahalli Division,